

T. 1 S., R. 31 E., W.M.

Chains		Feet
	Land; hilly. Soil; good 2nd rate.	+250
	E. on a random line bet. Secs. 22 & 27.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line, 20 lks. S. of Cor. to Secs. 22, 23, 26 & 27., from which Cor., I run S. 89° 57' W. on a true line bet. Secs. 22 & 27. Descend hill.	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
79.80	The Cor. to Secs. 21, 22, 27 & 28. Land; rolling. Soil; good 2nd rate.	-125
	N. bet. Secs. 21 & 22. Var. 27° E.	
13.00	Ravine brs. E. Ascend hill.	-100
40.00	Set stone, 16 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 26 x 12 x 8 for Cor. to Secs. 15, 16, 21 & 22. Land; hilly. Soil; 3rd rate.	+250
	E. on a random line bet. Secs. 15 & 22.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.64	Intersect N. & S. line at Cor. to Secs. 14, 15, 22 & 23, from which Cor., I run W. on a true line bet. Secs. 15 & 22.	
39.82	Set stone, 17 x 11 x 5 for $\frac{1}{4}$ Sec. Cor.	
79.64	The Cor. to Secs. 15, 16, 21 & 22. Land; rolling. Soil; 2nd rate, stony.	