

T. 1 S., R. 31 E., W.M.

Chains		Feet
	W. on a true line bet. Secs. 3 & 10.	
39.93	Set stone, 18 x 15 x 10 for $\frac{1}{4}$ Sec. Cor.	
79.87	The Cor. to Secs. 3, 4, 9 & 10.	
	Land; rolling.	
	Soil; 2nd rate.	
<hr/>		
	N. on a random line bet. Secs. 3 & 4.	
	Var. 19° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.32	Intersect N. Bdy., 12 lks. W. of Cor. to Secs. 3 & 4, from which, I run S.0° 5' W. on a true line bet. Secs. 3 & 4.	
40.32	Set stone, 18 x 10 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.32	The Cor. to Secs. 3, 4, 9 & 10.	
	Land; gently rolling.	
	Soil; good 2nd rate, very fine grass.	
	Nov. 14, 1864.	
<hr/>		
	N. bet. Secs. 32 & 33.	
30.00	Ravine brs. N.E.	
40.00	Set stone, 18 x 16 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 16 x 12 x 5 for Cor. to Secs. 32, 33, 28 & 29.	
	Land; rough and broken.	
	Soil; 2nd rate.	
<hr/>		
	E. on a random line bet. Secs. 28 & 33.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.64	Intersect N. & S. line at Cor. to Secs. 27, 28, 33 & 34, from which, I run W. on a true line bet. Secs. 28 & 33.	
39.82	Set stone, 15 x 12 x 10 for $\frac{1}{4}$ Sec. Cor.	
50.00	Ravine brs. N.E.	
79.64	The Cor. to Secs. 32, 33, 28 & 29.	
	Land; rolling, sloping N. Soil: good 2nd rate.	