

E. Bdy., T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. on E. Bdy. of Sec. 13 Var. 20° E.	
18.00	Ravine brs. N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
62.72	Ravine brs. W.	
80.00	Set post for Cor. to Secs. 7, 12, 13 & 18 in mound of earth, with charred stake, pits, trench, etc. as per instructions.	
	Land; hilly. Soil; good 2nd rate.	
	N. on E. Bdy. of Sec. 12. Var. 19° 30' E.	
	Descend hill.	
24.40	Ravine brs. N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 1, 6, 7 & 12, in mound of earth with charred stake, pits, trench, etc., as per instructions.	+400
	Land; gently rolling. Soil; good 2nd rate.	
	N. on E. Bdy. of Sec. 1. Var. 19° 30' E.	
21.50	Foot of hill, dry bed of creek, course N.W. Ascend hill.	-200
30.00	Top of hill	+300
40.00	Set stone, 16 x 12 x 10 ins. for $\frac{1}{4}$ Sec. Cor.	
81.00	Intersect Base Line, 18.00 chs. W. of Tp. Standard Cor. & build mound of stone.	
	Land; hill on S. half-mile, on N. half mile, level. Soil; good 2nd rate.	
	Subdivisional lines, T. 1 S., R. 32 E., W.M.	