

Subdivisional lines, T. 1 S., R. 32 E., W.M.  
 As surveyed by Daniel Chaplin, Deputy Surveyor  
 Under Contract No. 107 and  
 Dated Sept. 21, 1864.

Chains		Feet
	N. bet. Secs. 35 & 36 Ascend hill.	
26.00	Road brs. N.W. & S.E.-Top of hill, descend	+300
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, etc., as per instructions.	
45.80	Foot of hill. Ascend hill.	-300
80.00	Set stone, 28 x 8 x 8 for Cor. to Secs. 25, 26, 35 & 36. Land; hilly. Soil; good 2nd rate.	
	E. on a random line bet. Secs. 25 & 36.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.18	Intersect E. Bdy. 50 lks. N. of Cor. to Secs. 36 & 25, from which, I run N.89° 39' W. on a true line bet. Secs. 25 & 36.	
30.00	Daily Road brs. N.W. & S.E. Ascend along N. slope of hill.	
40.09	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with pits, charred stake, etc., as per instructions.	
80.18	The Cor. to Secs. 25, 26, 35 & 36. Land; hilly. Soil; good 2nd rate.	+300
	N. bet. Secs. 25 & 26. Var. 19 $\frac{1}{4}$ ° E.	
31.92	Road brs. N.W. & S.E.	
34.00	Ravine brs. N.W. & S.E., foot of hill, ascend.	
40.00	Set stone, 16 x 9 x 9 for $\frac{1}{4}$ Sec. Cor.	
65.00	Top of hill brs. N.W. & S.E. Descend.	
80.00	Set stone, 14 x 8 x 6 for Cor. to Secs. 23, 24, 25 & 26. Land; hilly. Soil; 2nd rate.	
	E. on a random line bet. Secs. 24 & 25.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect E. Bdy. 20 lks. S. of Cor. to Secs. 24 & 25, from	