

## Subdivisional lines; T. 1 S., R. 32 E., W.M.

Chains		Feet
	which, I run	
	N.89° 31' W. on a true line bet. Secs. 24 & 25. Ascend hill	
16.00	18.00 Top of hill, brs. N. & S. Descend.	+150
	40.00 Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with pits, charred stake, etc., as per instructions.	
	46.50 Deep ravine, course N. Ascend	-400
	80.00 The Sec. Cor.	+600
	Land; hilly.	
	Soil; 2nd rate.	
	N. bet. Secs. 23 & 24.	
	Var. 17 $\frac{1}{2}$ ° E.	
	Descend hill.	
	39.50 Road brs. E. & W.	
	40.00 Set stone, 21 x 8 x 6 for $\frac{1}{4}$ Sec. Cor. Foot of hill.	- 500
	43.60 Stewart Creek, dry bed, runs N.W. Ascend hill	
	65.00 Top of hill, brs. E. & W. Descend.	+450
	80.00 Set post for Cor. to Secs. 13, 14, 23 & 24, in mound of earth, with charred stake, pits, etc. as per instruc- tions.	-160
	Land; hilly.	
	Soil; 2nd rate.	
	E. on a random line bet. Secs. 13 & 24.	
	40.00 Set temp. $\frac{1}{4}$ Sec. Cor.	
	79.76 Intersect E. Bdy., 39 lks. N. of Cor. to Secs. 13 & 24, from which, I run	
	N.89° 47' on a true line bet. Secs. 13 & 24. Descend hill.	
	25.00 Ravine brs. N.	
	39.88 Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with pits, charred stake, etc., as per instructions.	
	79.76 The Cor. to Secs. 13, 14, 23 & 24.	
	Land; hilly, mostly N. slope of hill.	
	Soil; 2nd rate.	