

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 65 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which, I run S.89° 32' W. on a true line bet. Secs. 26 & 35. Descend hill.	
40.00	Set stone, 16 x 10 x 4 ins. for $\frac{1}{4}$ Sec. Cor.	
52.00	Road brs. N.W. & S.E.	
52.25	Ravine brs. N.W. Foot of hill. Ascend.	
80.00	The Cor. to Secs. 34, 35, 26 & 27. Land; hilly Soil; good 2nd rate. Fine grass.	
N. bet. Secs. 26 & 27. Var. 19 $\frac{1}{4}$ ° E. Descend hill.		
24.70	Road brs. N.W. & S.E.	
27.50	Ravine brs. N.W. Foot of hill, Ascend.	
40.00	Set stone, 18 x 7 x 6 for $\frac{1}{4}$ Sec. Cor.	
50.00	Top of hill, brs. E. & W. Descend.	
80.00	Set post for Cor. to Secs. 22, 23, 26 & 27, in mound of earth, with charred stake, pits, etc., as per instructions. Land; gently rolling. Soil; good 2nd rate.	
E. on a random line bet. Secs. 23 & 26.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line at post Cor. to Secs. 23, 24, 25 and 26, from which, I run W. on a true line bet. Secs. 23 & 26. Descend hill.	
39.90	Set stone, 16 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	
47.00	Ravine brs. N.W. Foot of hill. Ascend	-300
56.00	Daily's Road brs. N.W. & S.E.	
79.80	The Cor. to Secs. 22, 23, 26 & 27	+300