

## Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
✓	N. bet. Secs. 9 & 10.	
	Var. 19° E.	
40.00	Set stone, 18 x 15 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 3, 4, 9 & 10, in mound, with charred stake, pits, etc., as per instructions.	
	Land; level.	
	Soil; 1st rate.	
✓	E. on a random line bet. Secs. 3 & 10.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersect N. & S. line at Cor. to Secs. 2, 3, 10 & 11, from which,	
	I run	
	W. on a true line bet. Secs. 3 & 10.	
39.80	Set stone, 17 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	
44.00	Stewart Creek, dry bed, course N.W.	
62.00	Road brs. N.E. & S.W.	
79.60	The Cor. to Secs. 3, 4, 9 & 10.	
	Land; level.	
	Soil; 1st rate.	
	N. on a random line bet. Secs. 3 & 4.	
	Var. 19 $\frac{1}{2}$ ° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. Bdy. of Tp., 70 lks. E. of Cor. to Secs. 3 & 4, from which Cor.,	
	I run	
	S.30° E. on a true line bet. Secs. 3 & 4.	
21.54	Leave field, brs. E. & W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	The Cor. to Secs. 3, 4, 9 & 10.	
	Land; gently rolling.	
	Soil; 1st rate.	