

T. 1 S., R. 32 E., W.M.

Chains	Feet
	From Cor. to Secs. 12 & 13, I run S. on random on E. Bdy. of Sec. 13. Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.40	I found Cor. to Secs. 13 & 24, a charred stake, in earth mound, with pits. 58 lks. W. of line, I Set a basalt stone, 14 x 14 x 12 ins., 9 ins. in ground for Cor. to Secs. 13 & 24, marked, 3 notches on N. & S. edges. Dug pits, 18 x 18 x 12 ins. N., S., and W. of Cor. $5\frac{1}{2}$ ft. dist. Raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Thence I run N. 25' E. on true line.
18.10	Little McKay Creek, dry, course W.
35.40	Summit of ridge.
39.60	To $\frac{1}{4}$ Sec. Cor., which is a post, 18 ins. above ground, 3 ins. sq., with pits and earth mound. I redug pits, 18 x 18 x 12 ins. N. & S. of Cor., $5\frac{1}{2}$ ft. dist. and raised earth mound, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.
79.40	To Cor. to Secs. 12 & 13. Land; rolling. Soil; 2nd rate. No timber, very little grass.
	From Cor. to Secs. 13 & 24, I run, S. on random on E. Bdy. of Sec. 24. Var. 18° 45' E.
40.19	I found $\frac{1}{4}$ Sec. Cor., 15 lks. W. of line. Cor. is basalt stone, 14 x 10 x 8 ins., marked $\frac{1}{4}$ on W. face in a stone mound. Thence, I run N. 13° E. on a true line.
19.19	Intersected U.R. Bdy. at Angle Cor. 38, which is a basalt stone, 12 x 12 x 12 ins., 8 ins. in ground, marked U.R.

- 2