

T. 1 S., R. 32 E., W.M.

Chains		Feet
79.60	<p>To Cor. to Secs. 13 & 34 on Tp. line.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>No timber, very little grass.</p>	
	<p>W. on a random bet. Secs. 13 & 12.</p> <p style="text-align: right;">Var. 20° 30' E.</p>	
40.00	Not finding any $\frac{1}{4}$ Sec. Cor. I set temp. one.	
78.40	<p>Found Cor. to Secs. 11, 12, 13 & 14, which is a stone, 12 x 12 x 8 ins. in a stone mound, 20 lks. Nief line.</p> <p>Thence I run, S. 89° 51' E. on a true line.</p>	
38.50	<p>By digging, I found a stone, 12 x 10 x 3 ins. laying on its flat side and covered with earth, marked $\frac{1}{4}$. I Set it 8 ins. in the ground, with $\frac{1}{4}$ to the N. and dug pits 18 x 18 x 12 ins. E. & W. of Cor., $5\frac{1}{2}$ ft. dist. and raised a mound, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.</p>	
78.40	<p>To Cor. to Secs. 12 & 13 and Tp. line.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>No timber, little grass.</p>	
	<p>S. on a random bet. Secs. 13 & 14</p>	
14.20	Intersect U. R. Bdy., set temp. Closing Cor.	
79.43	<p>I found pits and mound at Cor. to Secs. 13, 14, 23 & 24.</p> <p>Thence N. on true line.</p>	
65.23	<p>Set basalt stone, 15 x 8 x 8 ins., 10 ins. in ground for Closing Cor., marked U.R. on E., C.C. on N. Raised a stone mound around it. Pits impracticable.</p>	
79.43	<p>To Cor. to Secs. 11, 12, 13 & 14.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Poor grass.</p>	
	<p>W. on a random bet. Secs. 11 & 14.</p> <p style="text-align: right;">Var. 24° E.</p>	