

T. 1 S., R. 32 E., W.M.

Chains		Feet
6.00	Set temp. Cor. on U.R. Bdy.	
39.75	I found a stone, 6 x 6 x 4 ins. above ground, 4 lks. S. of line. I dug pits E. & <sup>W</sup> N. of Cor., 18 x 18 x 12 ins., 5½ ft. dist. and raised earth mound 1½ ft. high, 3½ ft. base alongside.	
	Thence I run,	
	N. 89° 57' E. on a true line.	
34.00	Intersect U.R. Bdy. at a point N.23 ° W., 23.36 chs. from ½ mile Cor. in the 87th mile.	
	Set a post. 3 ft. long, 3ins. sq., 2 ft. in ground, which I marked U.R. C.C. on E. side for Closing Cor. to Secs. 11 & 14. Dug pits, 18 x 18 x 12 ins. N., S. & E. of post and raised mound of earth, 1½ ft. high, 3½ ft. base alongside.	
39.75	To Cor. to Secs. 11, 12, 13 & 14. Land; rolling. Soil; 1st rate. No timber, grass poor.	
	N. on random bet. Secs. 11 & 12. Var. 24° E.	
39.75	Found ¼ Sec. Cor.	
79.60	To Cor. to Secs. 1, 2, 11 & 12. I found charred stake, with pits and earth mound and see a basalt stone, 12 x 9 x 7 ins., 8 ins. in the ground, marked, 5 notches on S. and 1 notch on E. edges. Dug pits, 18 x 18 x 12 ins. in each Sec., 5½ ft. dist. and raised earth mound, 2 ft. high, 4½ ft. base alongside.	
	Thence I run	
	S. on true line	
39.85	To ¼ Sec. Cor., which is a basalt stone, 18 x 16 x 10 ins. marked ¼ on W. face with stone mound around it.	
79.60	To Cor. to Secs. 11, 12, 13 & 14. Land; rolling. Soil; 1st & 2nd rate.	