

T. 1 S., R. 33 E., W.M.

| Chains |   | Feet |
|--------|---|------|
|        | W. on a true line bet. Secs. 5 & 32.<br>Var. 22 ° E.  |      |
| 24.75  | Head of canyon, course N.   | -100 |
| 36.00  | Summit  | +100 |
| 40.00  | Set a basalt stone, 14 x 10 x 8 ins., 9 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.   |      |
| 50.00  | Canyon, course N.   | -100 |
| 70.00  | Summit of divide bet. McKay and Stewart Creeks<br>Intersect U.R. Bdy., 17.66 chs. N. 43° 30' E. of 78th mile Cor. and at 17th $\Delta$ Cor., which is a stone, 10 x 10 x 10 ins., 7 ins. in ground, marked U.R. $\Delta$ C.C., in a mound of stone. | +300 |
| 80.00  | Set a basalt stone, 16 x 12 x 8 ins., 11 ins. in ground for Cor. to Secs. 5, 6, 31 & 32, marked 5 notches on E. and 1 notch on W. edges. Raised mound of stone alongside. Pits impracticable.   | - 50 |
|        | Land; mountainous, 80.00 chs.<br>Soil; rocky, 4th rate.<br>No timber, good bunch grass.   |      |
| <hr/>  |   |      |
|        | W. on true line bet. Secs. 6 & 31.<br>Var. 25 ° E.  |      |
| 6.00   | Canyon, course N.   | -200 |
| 11.50  | Summit " "  | +100 |
| 40.00  | Set basalt stone, 16 x 10 x 6 ins., 11 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.  |      |
| 43.85  | Canyon, course N.   | -200 |
| 64.00  | Summit " "  | +350 |
| 80.00  | Canyon " "  | -400 |
| 100.00 | Ridge " "   | +300 |
| 134.55 | To W. Bdy., 5.64 chs. S. of Cor. to Tps. 1 & 2, S., R. 32 E., which is a post in stone mound. I set a basalt stone, 20 x 12 x 8 ins., 15 ins. in ground for Closing   |      |