

Tp. 1 S., R. 33 E., W.M.

Chains		Feet
40.00	Set a basalt stone, 9 x 8 x 7 ins., 6 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised a mound of stone alongside. Pits impracticable.	
43.00	Top of mountain	+90
47.00	Descend	
80.00	Set a post, 4 ft. long, 4 ins. sq., 2 ft. in ground for Cor. to Secs. 19, 24, 25 & 30., marked T.1 S., S.19 on N.E., R.34 E., S.30 on S.E., R.33 E., S.25 on S.W. and S.24 on N.W. faces, with 2 notches on the S. and 4 notches on the N. edges, from which, A pine, 20 ins. diam., brs. N.45° E., 108 lks. dist., marked T.1 S., R.34 E., S.19, B.T. A pine, 24 ins. diam., brs. S.60° E., 55 lks. dist., marked S.30, B.T. A pine, 26 ins. diam., brs. S.87° W., 50 lks. dist., marked R.33 E., S.25, B.T. A pine, 18 ins. diam., brs. N.30° W., 57 lks. dist., marked S.24, B.T. Land; mountainous, 80 chs. Scattering pine timber in canyons. Soil; 4th rate.	
	N. bet. Secs. 19 & 24. Var. 10° 45' E. Enter pine timber.	
7.00	Canyon- Creek with water in holes.	-250
10.00	Leave timber	
40.00	Set a basalt stone, 14 x 12 x 8 ins., 9 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.	
60.00	Summit, course E.	+35
63.00	Gulch, " "	-100
80.00	Set a post, 48 x 4 x 4 ins., 2 ft. in ground for Cor. to Secs. 13, 18, 19 & 24, marked T.1 S., R.34 E., S.18 on N.E., S.19 on S.E., R.33 E., S.13 on N.W. and S.24 on S.W. faces, with 3 notches on N. & S. edges, from which,	