

T. 1 S., R. 33 E., W.M.

Chains	Feet	
<p>A pine, 12 ins. diam., brs. N. 80° E., 133 lks. dist., marked T. 1 S., R. 34 E., S. 18, B.T.</p> <p>A pine, 4 ins. diam., brs. S. 45 ° E., 38 lks. dist., marked S. 19, B.T.</p> <p>No other trees in limits. Dug pits, 18 x 18 x 12 ins. in each Sec., 5½ Ft. dist., raised mound of earth, 2 ft. high, 4½ ft. base alongside.</p> <p>Land; mountainous, 80 chs.</p> <p>Timber; pine, 10 chs.</p> <p>Soil; rocky, 4th rate.</p>		
N. bet. Secs. 13 & 18.		
Var. 18° 45' E.		
13.50	Canyon, course E.	-600
28.50	Top of Ridge	+600
39.00	Dry gulch, course E.	-400
40.00	<p>A stone, 4 x 4 x 3 ft. above ground, which I marked ¼ on W. face and X on top at exact Cor. point for ¼ Sec. Cor. Raised a mound of stone alongside. Pits impracticable.</p>	
48.00	Gulch, course E.	-200
60.00	Ridge " "	+400
80.00	<p>Set a basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for Cor. to Secs. 7, 12, 13 &amp; 18, marked with 4 notches on S. and 2 on N. edges. Raised a mound of stone alongside. Pits impracticable.</p> <p>Land; mountainous, 80 chs.</p> <p>Soil; rocky, 4th rate.</p> <p>No timber, good bunch grass.</p>	
<p>I tested my compass at this place by taking an observation on Polaris and found it to be correct.</p>		
N. bet. Secs. 7 & 12.		
Var. 19° E.		
21.50	Touch McKay Creek, 20 lks. wide, course N. Enter timber.	-150