

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
39.40	Indian Trail, course N.W. & S.E.	
40.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
78.00	Leave table land.	
80.00	To Cor. to Secs. 15, 16, 21 & 22 Land; mostly level, mountainous, 15 chs. Soil; 2nd rate. Covered with bunchgrass and sunflowers.	- 50
	W. on a true line bet. Secs. 16 & 21. Var. 21° 15' E.	
32.50	Canyon, course N.	-150
40.00	Set basalt stone, 12 x 10 x 10 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
46.00	Top of ridge	+150
59.85	Canyon, course N.	-100
75.05	Intersect U.R. Bdy., S. 50° E. of 82nd mile Cor., dist 857 chs., set basalt stone, 10 x 10 x 10 ins., 6 ins. in ground, for Closing Cor. to Secs. 16 & 21, marked U.R. C.C. on E. face. Raised mound of stone around it. Pits impracticable.	
80.00	Set a basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Cor. to Secs. 16, 17, 20 & 21, marked, 3 notches on S., and 4 notches on E. edges. Raised mound of stone around it. Pits impracticable. Land; mountainous, 75.05 chs. Soil; 3rd rate. Good bunchgrass.	
	N. bet. Secs. 15 & 16. Var. 21° 15' E.	
12.50	Canyon, course W.	-350
25.00	Top of ridge	+400
34.00	Gulch, course W.	-250