

## Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	N. on true line bet. Secs. 3 & 4. Var. 19° 30' E.	
3.75	Enter field.	
11.00	Leave field, McKay Creek, 40 lks. wide, course W.	
28.00	Leave bottom.	
40.00	Set basalt stone, 16 x 14 x 12 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
47.00	Top of ridge	+300
86.10	Intersect Base Line, 390 lks. W. of $\frac{1}{4}$ Sec. Corneon S. Bdy. Sec. 34. Set a basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Closing Cor. to Secs. 3 & 4, marked, 3 not- ches on E. & W. C.C. on S. faces, raised mound of stone around it. Pits impracticable. Bottom land; 1st rate. 58.10 chs., mountainous, 4th rate. Cottonwood and thorn in bottoms. Grass on the hills.	
	From Cor. to Secs. 4, 5, 32 & 33 on S. Bdy. of Tp. I run N. bet. Secs. 32 & 33. Var. 22° E.	
37.50	Canyon, course N.E.	-500
40.00	Set a basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
66.75	Road on ridge	+500
72.30	To U.R. Bdy., N. 45 $\frac{1}{2}$ ° E. of $\frac{1}{2}$ mile Cor. on 80th mile, dist. .88 chs. Set a basalt stone. 18 x 18 x 14 ins., 13 ins. in ground, for Closing Cor. to Secs. 32, marked U.R. CC. on S. face. Raise mound of stone around it. Pits imprac- ticable. On Bdy. line.	
80.00	Set basalt stone, 12 x 9 x 7 ins. for Cor. to Secs. 28, 29, 32 & 33, marked 1 notch on S. and 4 notches & U.R. on E. Raised mound of stone around it. Pits impracticable. Land; mountainous, 80.00 chs. Soil; 3rd rate. Good bunch grass.	