

## Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
85.95	<p>Intersect Base Line, 380 lks. W. of <math>\frac{1}{4}</math> Sec. Cor. on S. Bdy. S.33. Set basalt stone, 14 x 12 x 12 ins., 8 ins. in ground, for Closing Cor. to Secs. 4 &amp; 5, marked 4 notches on E. and 2 notches on W. edges. C. Cor. S. Raised a mound of stone alongside.</p> <p>Land; rolling.</p> <p>Soil; 1st rate on 1st half, 3rd rate on 2nd half.</p> <p>Cottonwood and thorn in bottom.</p> <p style="text-align: right;">July 18, 1887.</p>	
6.00	<p>W. on a true line bet. Secs. 8 &amp; 17.</p> <p style="text-align: right;">Var. 26° E.</p> <p>Ascend.</p> <p>Top of ridge.</p>	+300
40.00	<p>Set basalt stone, 14 x 10 x 8 ins., 8 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{2}</math> on N. face. Raised mound of stone around it. Pits impracticable.</p>	
65.00	<p>Summit</p>	+400
80.00	<p>Set basalt stone, 10 x 10 x 8 ins., 6 ins. in ground, for Cor. to Secs. 7, 8, 17 &amp; 18, marked, 4 notches on S., and 5 notches on E. edges. Raised mound of stone around it. Pits impracticable.</p> <p>Land; mountainous, 80 chs.</p> <p>Soil; rocky, 4th rate.</p> <p>Poor bunch grass.</p>	
3.00	<p>S. on a true line bet. Secs. 17 &amp; 18.</p> <p style="text-align: right;">Var. 19° 15' E.</p> <p>Summit of ridge</p>	+600
32.00	<p>Little McKay Creek ( dry)</p>	-400
40.00	<p>Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{2}</math> on W. face. Raised mound of stone around it. Pits impracticable.</p>	
63.50	<p>Intersect U.R. Bdy., 610 lks. N. 89° 30' W. of 83rd mile Cor. Set basalt stone, 10 x 10 x 10 ins., 6 ins. in ground, fo</p>	