

Subdivisional Lines, T.1 S., R. 33 E., W.M.

Chains		
40.00	Set basalt stone, 12 x 10 x 10 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	-100
43.50	Gulch, course N.	- 50
70.00	Summit, course N.	+200
84.50	Gulch, course N.W.	-200
135.00	Intersect Tp. line, 620 lks. S. of Cor. to Secs. 12 & 13, T.1 S., R. 32 E.	
	Set basalt stone, 16 x 10 x 5 ins., 11 ins. in ground, for Closing Cor. to Secs. 7 & 18, marked C.C., 4 notches on S. and 2 notches on E. edges. Raised mound of stone around it. Pits impracticable.	
	Land; mountainous, 135 chs.	+150
	Soil; 2nd rate.	
	Good bunch grass.	
	<hr/>	
	N. bet. Secs. 7 & 8.	
	Var. 19° 15' E.	
	Descend.	
7.50	Gulch, course N.W.	-100
18.00	Top of ridge, course N.W.	+100
40.00	Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 ins. N. & S. of Cor., $5\frac{1}{2}$ ft. dist. raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.	
44.00	Gulch	-300
55.00	Top of ridge, course N.W.	+200
72.75	Gulch, course N.W.	-300
80.00	Set basalt stone, 14 x 10 x 10 ins., 8 ins. in ground, for Cor. to Secs. 5, 6, 7 & 8, marked 5 notches on S. & E. edges. Raised mound of stone around it. Pits impracticable.	
	Land; mountainous, 80 chs.	
	Soil; 2nd rate. No grass, no timber, some few weeds.	