

Subdivisions, T. 1 S., R. 33 E., W.M.

Chains		Feet
8.00	Top of ridge falls S. Descend	
19.00	Ravine, course S.W. Ascend hill.	
29.00	Top of hill drops S.	
37.64	<p>Intersect Res. Bdy. at Closing Cor. to Secs. 18 & 19, which is a basalt stone, 8 x 8 x 7 ins. in mound of stone, & marked X on top, U.R.C.C. on W. face.</p> <p style="text-align: right;">Var. 20° 00' E.</p> <p>Land; mountainous and stony, 37.64 chs.</p> <p>Soil; 4th rate. No timber.</p> <p style="text-align: right;">Sept. 10, 1890</p>	
	<p>From Closing Cor. to Secs. 28 & 29 on Res. Bdy., which is a basalt stone, 12 x 12 x 9 ins., marked U.R.C.C. 80 M.</p> <p>I run, thence,</p> <p>N. bet. Secs. 28 & 29.</p> <p style="text-align: right;">Var. 21° E.</p> <p>Descend.</p>	
8.61	<p>Set basalt stone, 15 x 6 x 6 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of Cor., $5\frac{1}{2}$ dist., and raised a mound of stone, covered with earth, 2 ft. high $4\frac{1}{2}$ ft. base over it, on hillside facing N.E.</p>	
13.36	Deep gulch, course N.W. Ascend steep hill.	
39.11	Summit. Descend 45°	+30
48.61	<p>Set basalt stone, 12 x 11 x 10 ins., 8 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29, marked, 4 notches on E. face and 2 notches on S. face; dug pits, 18 x 18 x 12 ins. in each Sec. Cor., $5\frac{1}{2}$ ft. dist., and raised a mound of earth and stone, 2 ft. high, $4\frac{1}{2}$ ft. base over Cor. on steep N.E. hillside.</p> <p>Land; mountainous, 48.61 chs.</p> <p>Soil; 3rd rate.</p> <p>Good grass on N. slopes. No timber.</p>	