

Subdivisions, Tp. 1 S., R. 33 E., W.M.

Chains		Feet
37.50	Summit of ridge falls W. Descend.	
39.04	Set a basalt stone, 10 x 8 x 7 ins., 7 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins. N. & S. of Cor., and raised a mound of stone covered with earth, 2 ft. high, $4\frac{1}{2}$ ft. base over Cor. on hillside facing S.W.	
42.75	Gulch, course W. Ascend hill.	
58.00	Summit drops W. Descend.	
70.20	Gulch, course W. Ascend steep hill.	
74.00	Summit falls W. Descend.	
77.40	Gulch, course N.W. Ascend.	
78.07	The Cor. to Secs. 20, 21, 28 & 29 Land; mountainous and stony, 78.07 chs. Soil; 4th rate. Good grass on N. slopes. No timber.	
	Sept. 11, 1890.	
	From Cor. to Secs. 5, 6, 31 & 32, on the S. Bdy. of the Tp., which is a basalt stone, 14 x 10 x 8 ins., marked X on top and 1 notch on W. face, in mound of stone, 1 ft. high, 2 ft. base on hillside facing N.W., (I cut 5 notches on E. face, set the Cor. stone, 10 ins. in ground, dug pits, 18 x 18 x 12 ins., E. & W. of Cor. $5\frac{1}{2}$ ft. dist. and raised mound of stone, covered with earth, 2 ft. high, $4\frac{1}{2}$ ft. base alongside.)	
	I run N. bet. Secs. 31 & 32	
	Var. 25° 30' E.	
	Descend.	
12.55	Enter dense brush on steep hillside.	
14.25	Deep ravine, course N.W.-Leave brush and ascend steep, stony hill.	
17.00	Summit falls N.W. Descend.	
21.00	Canyon, course N.W. Ascend steep stony hill.	
34.00	Summit. Descend.	
39.20	Ravine, course N.W. Ascend.	