

Subdivisional Allotments, T.1 S., R. 33 E., W.M.
Section 4.

Chains		Feet
	<p>Land; smooth, mountainous. Soil; 1st rate, rocky. Good grass.</p>	
<u>Section 5.</u>		
	<p>From the $\frac{1}{4}$ Sec. Cor. bet. Secs. 5 & 6, which is a basalt stone, 12 x 10 x 10 ins., 8 ins. in ground, marked $\frac{1}{4}$ on W. face, with pits, 18 x 18 x 12 ins., N. & S. of stone, $5\frac{1}{2}$ ft. dist., a mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.</p> <p>I run, N. on true line bet. Secs. 5 & 6. Var. 20° E.</p> <p>Descend through grainfield.</p>	
8.40	Road, course E. & W.	
8.50	Fence, course E. & W. Enter garden.	
10.00	<p>Set basalt stone, 10 x 8 x 7 ins., 7 ins. in ground for 1/16 Sec. Cor., marked 1/16 on W. face; dug pits, 18 x 18 x 12 ins., E. & W of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Soil; 1st rate. Cultivated.</p>	
	<p>From the $\frac{1}{4}$ Sec. Cor. bet. Sec. 5 & 6, I run, S. on true line bet. Secs. 5 & 6. Var. 20° E.</p>	
7.15	Fence, course E. & W.	
10.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for 1/16 Sec. Cor., marked 1/16 S. on W. face; dug pits, 18 x 18 x 12 ins., E. & W. of post, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p> <p>Land; N. face of mountain down to creek bottom. Soil; 1st rate., cultivated.</p>	