

Subdivisional Allotments, T. 1 S., R. 33 E., W.M.
Section 6.

Chains		Feet
	A balm, 6 ins. diam., brs. S.20° W., 40 lks. dist., marked 1/16 S. B.T.	
23.00	McKay creek, 20 lks. wide, course S.W.	
25.00	Mc Kay creek, 20 lks. wide, course N.W. Following down creek to	
32.50	Leave creek.	
33.50	Cross fence, course N.E: & S.W.	
37.50	Leave brush.	
40.00	Set stone, 19 x 8 x 7 ins., 10 ins. in ground for 1/16 Sec. Cor., marked 1/16 on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of stone, 5½ ft. dist. and raised mound of earth, 1½ ft. high, 3½ ft. base over stone. Land; creek bottom, level and rocky. Timber; balm and undergrowth.	
	From the 1/16 Sec. Cor. 10.00 chs. N. and 40 chs. W. of the ¼ Sec. Cor. bet. Secs. 5 & 6, I run, S. on true line in Sec.6.	
	Var. 15° E.	
4.50	Fence, course E. & W.	
4.80	McKay creek, 40 lks. wide, course W.	
14.00	Road, course E. & W.	
16.50	Leave timber and undergrowth.	
20.00	Deposited a marked stone, 12 ins. in ground for 1/16 Sec. Cor.; dug pits, 18 x 18 x 12 ins. E. & W. of Cor., 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake, 2 ft. long, 2 ins. sq. 12 ins. in ground, marked 1/16 on W. face. Land; river bottom and side hill. Soil; gravelly in bottom, 2nd rate on side hill.	
	From the 1/16 Sec. Cor., 40 chs. W. and 10.00 chs. S. of ¼ Sec. Cor. bet. Secs. 5 & 6, I run E. on random line in Sec. 6.	