

Subdivisional Allotments, T. 1 S., R. 33 E., W.M.

Section 6.

Chains		Feet
	Var. 20° E.	
20.00	Set temp. 1/16 Sec. Cor.	
39.90	Intersect the N. & S. line 5 lks. N. of 1/16 Sec. Cor., 10 chs. S. of the 1/4 Sec. Cor. bet. Secs. 5 & 6. Thence I run N.89° 56' W. on true line in Sec. 6.	
	Var. 20° E.	
19.95	Deposited marked stone, 12 ins. in ground for 1/16 Sec. Cor. Dug pits, 18 x 18 x 12 ins. E. & W. of Cor., 5 1/2 ft. dist. and raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it. In the E. pit drove a stake, 2 ft. long, 2 ins. sq., 12 ins. in ground, marked 1/16 S. on N. face.	
25.95	Fence, course N.85° E.	
36.00	Gulch, course N.	75
39.90	To 1/16 Sec. Cor., 10 chs. S. of the center of Sec. 6. Land; slopes to North. Soil; 1st rate. Good grass.	
	June 25, 1889	
<u>General Description</u>		
<u>Secs. 3, 4, 5 & 6.</u>		
The allotments in Secs. 3, 4, 5 & 6 are situated principally on the S. side of McKay Creek, and are mostly rich agriculture land, with settlers.		
Indians in each section, cultivating a part of the land.		
Grain and grass, with timber, along creek, are the principal productions.		