

T. 1 S., R.34 E., W.M.

Chains		Feet.
	<p>A pine, 20 ins. diam., brs. N.15° W., 81 lks. dist., marked T.1 S.,R.34 E.,S.13,B.T.</p> <p>No other trees in limits. Raised mound of stone alongside. Pits impracticable.</p> <p>Land; mountainous, 80.00 chs.</p> <p>Scattering pine timber and good bunch grass.</p> <p>Soil; 2nd rate.</p>	
<p>15.00</p> <p>40.00</p> <p>79.00</p> <p>80.00</p>	<p>N. on E. Bdy. of Sec. 13.</p> <p style="text-align: right;">Var. 19° 30' E.</p> <p>Dry branch, course W.</p> <p>Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which,</p> <p>A pine, 20 ins. diam., brs. N.25° E., 83 lks. dist., marked $\frac{1}{4}$ S.,B.T.</p> <p>A pine,20 ins. diam., brs. N. 45° W., 125 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>Dry branch, course W.</p> <p>Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for Cor. to Secs. 7, 12,13 & 18, marked 4 notches on S. and two on N. edges, from which,</p> <p>A pine, 12 ins. diam., brs. N.20° W., 61 lks. dist., marked T.1 S.,R.34 E.,S.12, B.T.</p> <p>A pine, 12 ins. diam., brs. S.72 ° E., 163 lks. dist., marked T.1 S.,R.35 E., S.18, B.T.</p> <p>No other trees in limits. Raised mound of stone alongside.</p> <p>Pits impracticable.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Scattering pine timber and good bunch grass.</p>	<p>-100</p>
<p>40.00</p>	<p>N. on E. Bdy. of Secs. 12.</p> <p style="text-align: right;">Var. 19° 20' E.</p> <p>Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on W. face, from which,</p> <p>A pine, 24 ins. diam., brs. N.20° E., 27 lks. dist.</p>	