

## Subdivisional Lines, T. 1 S., R. 34 E., W. M.

Chains		Feet
20.00	Branch, water in holes, course S.W.	-100
40.00	Set basalt stone, 20 x 18 x 16 ins., 15 ins. in ground marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	+100
50.50	Touched dry branch Leave branch and ascend.	-100
80.00	Set stone (basalt), 20 x 10 x 10 ins., 15 ins. in ground, marked 4 notches on S. 1 notch on E. edges, for Cor. to Secs. 11, 12, 13 & 14. Raised mound of stone around it. Pits impracticable.  Land; rough and mountainous, 80 chs. Scattering pine timber in canyons. Soil; 3rd rate.	
E. on random bet. Secs. 12 & 13. Var. 19° 10' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.90	Intersect Tp line, 36 lks. S. of Cor. to Secs. 7, 12, 13 and 18. Thence I run, S. 89° 45' W. on a true line.	
2.10	Gulch, course S.W.	- 50
10.10	Leave gulch.	
39.95	Set post, 3 ft. long, 3 ins. sq., 2 ft. in ground, marked $\frac{1}{4}$ S. on N. face, for $\frac{1}{4}$ Sec. Cor., from which, A pine, 12 ins. diam., brs. S. 24° W., 37 lks. dist. marked $\frac{1}{4}$ S, B.T., also A pine, 24 ins. diam., brs. N. 70° W., 13 lks. dist. marked $\frac{1}{4}$ S., B.T.	
71.50	Canyon, course S.	-200
79.90	Cor. to Secs. 11, 12, 13 & 14. Land; most level. Scattering pine timber. Good bunch grass. Soil; 2nd rate.	