

## Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	N. bet. Secs. 11 & 12. Var. 19° 10' E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 2 ft. in ground, marked $\frac{1}{4}$ S. on W. face for $\frac{1}{4}$ Sec. Cor., from which, A pine, 12 ins. in diam., brs. S. 40° E., 36 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 14 ins. diam., brs. S. 45° W., 33 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for Cor. to Secs. 1, 2, 11 & 12, marked, T.1 S., S.1 T.1 S., S.1 on N.E. S.2 on N.W. R.34 E., S.11 on S.W. S.12 on S.E. with 5 notches on S., 1 notch on E. edges, from which, A pine, 6 ins. diam., brs. N. 70° E., 53 lks. dist., marked T.1 S., R.34 E., S.1, B.T. A pine, 14 ins. diam., brs. S. 45° E., 87 lks. dist., marked T.1 S., R.34 E., S.12, B.T. A pine, 8 ins. diam., brs. S. 20° W., 87 lks. dist., marked T.1 S., R.34 E., S.11, B.T. A pine, 16 ins. diam., brs. N. 34° W., 63 lks. dist., marked T.1 S., R.34 E., S.2, B.T. Land; level. Pine timber and undergrowth. Soil; 4th rate.	
	E. on random bet. Secs. 1 & 12. Var. 23° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.43	Intersect Tp. line, 25 lks. S. of Cor. to Secs. 1, 6, 7 & 12 Thence I run, S. 89° 49' W. on true line.	
10.00	Gulch, course N.	-80
40.22	Marked a fir tree, 8 ins. diam., $\frac{1}{4}$ S. on N. face for $\frac{1}{4}$ Sec. Cor., from which,	