

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	From the Cor. to Secs. 2, 3, 34 & 35 on the S. Bdy. of Tp. I run, N. bet. Secs. 34 & 35. Var. 18° E.	
40.00	Set basalt stone, 18 x 12 x 8 ins., 12 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on W. face. Raised a stone mound around it. Pits impracticable.	-300
59.25	Canyon, course N.20° W.	-900
80.00	Set basalt stone, 10 x 9 x 8 ins., 6 ins. in ground for Cor. to Secs. 26, 27, 34 & 35, marked 1 notch on S. & 2 on E. edges. Raised a stone mound around it, from which, A pine, 10 ins. diam, brs. N. 40° W., 160 lks. dist. marked T.1 S., R.34 E., S.27,B.T. No other trees in limits. Land; mountainous, 80.00 chs. Soil; rocky, 4th rate. Some grass.	
	E. on random bet. Secs. 26 & 35. Var. 21 1/4° E.	
40.00	Set temp. 1/4 Sec. Cor.	
80.20	Intersect N. & S. line, 25 lks. N. of Cor. to Secs. 25, 26, 35 & 36. Thence, I run, N. 89° 49' W. on true line	
18.70	Canyon, course N.W.	-600
35.00	Summit of ridge, course N. Descend.	+500
40.10	Set basalt stone, 15 x 10 x 8 ins., 12 ins. in ground for 1/4 Sec. Cor., marked 1/4 on N. face. Raised stone mound around it. Pits impracticable.	+200
80.20	To Cor. to Secs. 26,27, 34 & 35 Land; mountainous, 80.20 chs. Soil; rocky, 4th rate. No timber, scattering bunch grass.	-400