

## Subdivisional Line, T. 1 S., R. 34 E., W.M.

Chains		Feet
	<p>with 4 notches on W. and 2 notches on E. edges. Raised mound of stone around it. Pits impracticable.</p> <p>Land; mostly level.</p> <p>Heavy pine timber, 84 chs.</p> <p>Soil; 3rd rate.</p>	
	From the Cor. to Secs. 3, 4, 33 & 34 on the S. Bdy. of Tp.	
	I run	
	N. bet. Secs. 33 & 34	
	Var. 17° 15' E.	
40.00	Set basalt stone, 14 x 12 x 8 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
50.85	Canyon and creek, course N.30° E.	-500
61.00	Gulch, course E.	
80.00	Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 27, 28, 33 & 34, marked, 1 notch on S. and 3 notches on E. Raised mound of stone around it. Pits impracticable.	+400
	Land; rough and mountainous, 80 chs.	
	Pine timber in canyons. Bunch grass.	
	Soil; 3rd rate.	
	E. on random bet. Secs. 27 & 34.	
	Var. 20° 15' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect N. & S. line, 47 lks. S. of Cor. to Secs. 26, 27, 34 & 35.	
	Thence I run	
	S. 89° 47' W. on true line	
5.50	Branch McKay Creek, course N., 5 lks. wide.	- 50
37.00	Summit of ridge, course N.	+100
39.85	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
65.75	Canyon and Creek, course N., 10 lks. wide.	-100