

Subdivisional Line, T. 1 S., R. 34 E., W.M.

Chains		Feet
	E. on random bet. Secs. 10 & 15. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.75	Intersect N. & S. line, 28 lks. S. of Cor. to Secs. 10, 11, 14 & 15. Thence I run, S. 89° 48' W. on true line.	
11.50	Branch, 5 lks. wide, course S.E.	-500
22.50	Top of ridge, course S.	+200
26.50	Ravine, course S.	-100
31.50	Top of hill	+600
39.87	Set basalt stone, 20 x 16 x 12 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
45.00	Canyon, course S.	-400
65.00	Enter pine timber, ascend	
79.75	To Cor. to Secs. 9, 10, 15 & 16. Land; rough and mountainous, 79.75 chs. Some pine timber. Good bunch grass. Soil; 3rd rate. July 5th, 1887.	
	N. bet. Secs. 9 & 10. Var. 19° E.	
3.00	Enter timber.	
10.00	Small prairie.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, marked $\frac{1}{4}$ S. on W. face, for $\frac{1}{4}$ Sec. Cor., from which, A pine, 14 ins. diam., brs. S. 85° E., 23 lks. dist., marked $\frac{1}{4}$ S., B.T., also A pine, 12 ins. diam., brs. N. 20° W., 16 lks. dist., marked $\frac{1}{4}$ S., B.T.	
55.00	Descend.	
60.55	Canyon, course N.	-200
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for Cor. to Secs. 3, 4, 9 & 10, marked,	