

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	N. bet. Secs. 3 & 4.	
	Var. 21° 10' E.	
18.00	Gulch, course W.	-100
22.00	Top of ridge	+100
40.00	Set post, 3 ft. long, 3 ins. sq., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 16 ins. diam., hrs. 23 ° E., 175 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 18 ins. diam., hrs. N.60° W., 218 lks. dist., marked $\frac{1}{4}$ S., B.T.	
60.00	Leave timber.	
84.50	Intersect Base Line, 485 lks. W. of $\frac{1}{4}$ Sec. Cor. on S. Bdy. of Sec. 34. Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Closing Cor. to Secs. 3 & 4, marked CC., with 3 notches on E. & W. edges, and raised mound of stone around it. Pits impracticable. Land; rolling, covered with scattering pine timber and bunch grass. Soil; 3rd rate.	
	From the Corner to Secs. 4, 5, 32 & 33 on the S. Bdy. of Tp. 1 run N. bet. Secs. 32 & 33.	
	Var. 24° 45' E.	
14.00	Summit of ridge, course N.E.	+400
37.00	Canyon, course N.E.	-500
40.00	Set basalt stone, 14 x 8 x 6 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
60.00	Gulch, course E.	- 60
65.00	" " "	-400
80.00	Set basalt stone, 20 x 8 x 6 ins., 15 ins. in ground, for Cor. to Secs. 28, 29, 32 & 33, marked, 1 notch on S. and 4 notches on E. edges. Raised mound of stone around it. Pits impracticable.	
	Land; rough and mountainous, 80 chs. Good bunch grass. Soil; 3rd rate.	