

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

| Chains | | Feet |
|--|---|------|
| | <p>$\frac{1}{4}$ Sec. Cor., from which, A pine, 14 ins. diam., brs. N.86°E., 70 lks. dist., marked $\frac{1}{4}$ S., B.T. No other tree in limits. Raised mound of stone around it. Pits impracticable.</p> | 50 |
| 41.50 | Gulch, course S. | 50 |
| 57.50 | Top of ridge, course N.W. | 800 |
| 79.70 | To Cor. to Secs. 5, 6, 7 & 8. Land; mountainous, 79.70 chs. Good bunch grass. Soil; 3rd rate. | |
| W. on random bet. Secs. 6 & 7 Var. 18° E. | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 82.10 | Intersect Tp. line, 19 lks. S. of Cor. to Secs. 1, 6, 7 and 12. Thence I run S.89° 52' E. on true line. | |
| 42.10 | Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable. Ascend. | |
| 82.10 | To Cor. to Secs. 5, 6, 7 & 8. Land; sloping to West. Good bunch grass. Soil; 3rd rate. | |
| N. on true line bet. Secs. 5 & 6. Var. 18° E. | | |
| 10.00 | Top of ridge, course W. | 400 |
| 15.00 | Canyon, course W. | 50 |
| 40.00 | Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable. | |
| 48.50 | Descend. | |