

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
59.00	Canyon, course N.W.	300
70.00	Top of ridge	
85.90	Intersect Base Line, 478 lks. W. of $\frac{1}{4}$ Sec. Cor. on S. Bdy. of Secs. 32 Set post; 48 x 4 x 4 ins., 2 ft. in ground for Closing Cor. to Secs. 5 & 6, marked, T.1 S.,R.34 E.,S.5 on S.E. S.6 on S.W. T.1 N.,R.34 E.,S.32 on N. C.C. on S. with 5 notches on E. edge 1 notch on W. edge, from which, A pine, 14 ins. diam., brs. S.42° E., 63 lks. dist., marked T.1 S.,R.34 E.,S.5, B.T. A pine, 6 ins. diam., brs. S.70° W., 23 lks. dist., marked T.1 S.,R.34 E.,S.6, B.T. A pine, 6 ins. diam., brs. N.45° W., 59 lks. dist., marked T.1 N.,R.34 E.,S.32, B.T. Land; mountainous, 85.90 chs. Scattering pine timber and bunch grass. Soil; 4th rate. July 8th, 1887.	

General Description

This Township is rough and mountainous. There is some good pine, fir and tamarack timber in the North portion. Cottonwood and dense under brush along the McKay Creek and its tributaries.

Nearly all of it is covered with good grass.

Soil, 3rd rate. Water plenty.

Resurvey Portion N. Bdy., T. 2 S., R.34 E., W.M.

As surveyed by L.E.Wilkes, U.S. Deputy Surveyor
Under Special Contract, dated Feb. 20, 1917.

From the Cor. of Tps. 1 & 2, Rs. 34 & 35 E., W. retracing