

Resurvey Portion N. Bdy. T. 2 S., R. 34 E., W.M.

| Chains | | Feet |
|--------|--|------|
| | <p>W.C. on S. face; and raise mound of stone, 4 ft. base, 2½ ft. high, N. of Cor.</p> <p>This Cor. is on top of high ridge, brs. N.20°E & S.20° W. Thence</p> <p>N.88°46'E., continuing my measurements.</p> <p>Descend 950 ft. over broken E. slope, through scattering timber.</p> | |
| 40.01 | <p>(40.00 chs. departure.)</p> <p>Set iron post, 3 ft. long, ½ in. diam., 26 ins. in ground, for ¼ Cor. of Sec. 3 only, with brass cap marked</p> | |
| | <p style="text-align: center;"> $\frac{1}{4}S3$ 1917 </p> | |
| | <p>from which,</p> <p style="padding-left: 40px;">A fir, 9 ins. diam., brs. S.32° E., 303 lks. dist., marked ¼ S. 3, B.T.</p> | |
| 42.74 | <p>A pine, 30 ins. diam., on line, marked with 2 notches on E. & W. sides.</p> | |
| 42.80½ | <p>Apportioned distance.</p> <p>Set red lava stone, 16 x 8 x 6 ins., 11 ins. in ground, for ¼ Cor. of Sec. 34 only, marked ¼ S.34 on N. face;</p> <p>from which,</p> <p style="padding-left: 40px;">A fir, 28 ins. diam., brs. N.20° E., 59 lks. dist., marked ¼ S.34, B.T.</p> | |
| 44.00 | <p>Johnson Creek, 25 lks. wide, course N., thence over bottom land.</p> | |
| 45.60 | <p>Leave bottom, brs. N. & S.; ascend 1050 ft. to</p> | |
| 79.00 | <p>Top of ridge, brs. N.30° W. and S.45° E.</p> | |
| 80.02 | <p>(80.00 chs. departure)</p> <p>Set iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground for Cor. of Secs. 2 & 3, with brass cap, marked</p> | |
| | <p style="text-align: center;"> $\frac{T1S}{S3 S2}$ T2S R34E 1917 </p> | |
| | <p>from which,</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., brs. S.80° E., 74 lks. dist. marked T.2 S., R.34 E., S.2, B.T.</p> | |