

E. Bdy., T.1 S., R.35 E., W.M.

Chains	Feet
	Soil; gravelly, 2nd rate. Timber; fir, pine and tamarack.
	N. bet. Sec. 25 & 30. Var. 20° E. Descend through dense timber.
7.50	Old road, course S.E. & N.W.
27.50	Ravine, course N.10° E.
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, on hillside, sloping N. in dense timber for ¼ Sec. Cor., marked ¼ S. on the E. & W. faces. A fir, 12 ins. diam., brs. N.47°W., 28 lks. dist., marked ¼ S., B.T. A pine, 5 ins. diam., brs. N.85°E., 29 lks. dist., marked ¼ S., B.T.
	Descend through heavy timber.
45.00	Bottom of canyon, course S.E. Ascend.
63.50	Bluff of rocks.
65.00	Enter thicket.
72.50	Top of hill.
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, on N. slope of hill, 100 ft. below summit in heavy timber for Cor. to Secs. 19, 24, 25 & 30, marked T.1 S., S.19 on N.E. R.36E., S.30 on S.E. R.35 E., S.25 on S.W. S.24 on N.W. faces, with 2 notches on S. and 4 notches on N. edges, from which, A fir, 18 ins. diam., brs. S.81°W., 28 lks. dist., marked T.1 S., R.35 E., S.25., B.T. A tamarack, 16 ins. diam., brs. S.49°E., 25 lks. dist., marked T.1 S., R.36E., S.30, B.T. A tamarack, 14 ins. diam., brs. N.47°E., 25 lks. dist., marked T.1 S., R.36E., S.19, B.T. A fir, 16 ins. diam., brs. N.58° W., 15 lks. dist.,