

E. Bdy. T.1 S., R.35 E., W.M.

Chains		Feet
	<p>marked T.1 S., R.35 E., S.24, B.T.</p> <p>Land; high, mountainous and broken.</p> <p>Soil; rocky, 4th rate,</p> <p>Timber; fir, pine and tamarack.</p>	
	N. bet. Secs. 19 & 24	
		Var. 20° E.
	Descend through heavy timber.	
5.00	Head of ravine, course N.E.	
34.00	Bottom of hollow; ascend.	
40.00	Set post, 4 ft. long, 4 ins. sq., 18 ins. in ground on E. slope in dense timber and underbrush for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S on E. & W. faces, from which,	
	A fir, 10 ins. diam., brs. N.58°E., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	A tamarack, 10 ins. diam., brs. N.85°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.	
		Var. 21° 15' E.
	Descend through dense timber and underbrush.	
67.75	Bottom of ravine, course N.E.	
68.75	Bed of dry creek. Course N.E.. Ascend through scattering timber	
80.00	Set post (and stone, 24 x 48 x 34), 4 ft. long, 4 ins sq. 24 ins. in ground, on steep hillside sloping W., 250 ft. above the bottom of ravine and 400 ft. below the summit for Cor. to Secs. 13, 18, 19 & 24. Post marked	
	T.1 S., S.18 on N.E.	
	R.36 E., S.19 on S.E.	
	R.35 E., S.24 on S.W.	
	S.13 on N.W. faces with	
	3 notches on N. & S. edges.	
	A pine, 14 ins. diam., brs. S.89° W., 162 lks. dist., marked T.1 S., R.35 E., S.24, B.T.	
	Land; mountainous and broken.	
	Soil; gravelly, 4th rate.	
	Timber; pine and fir.	