

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
<p>13 ins. diam., marked, T.1 S., T.1 S., S.7 on E. R.36 E., S.18 on S.E. R.35 E., S.13 on S.W. and S.12 on N.W. faces, with 4 notches on S. and 2 notches on W. edges, from which, A fir, 11 ins. diam., brs. S.10°W., 17 lks. dist., marked T.1 S., R.35 E., S.13, B.T. A fir, 10 ins. diam., brs. S.88°E., 14 lks. dist., marked T.1 S., R.36 E., S.18, B.T. A fir, 10 ins. diam., brs. N.13°E., 17 lks. dist., marked T.1 S., R.36 E., S.7, B.T. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 12 & 13, marked C.C. on W. C.C. on W. T.1 S., R.35 E., S.12 on N. T.1 S., R.35 E., S.13 on S., with 4 notches on S. and 2 notches on W. edges, from which, A fir, 18 ins. diam., brs. N.57°W., 53 lks. dist., marked C.C., T.1 S., R.35 E., S.12, B.T. A fir, 15 ins. diam. brs. S.33° W., 25 lks. dist., marked C.C., T.1 S., R.35 E., S.13, B.T. A tamarack, 9 ins. diam., brs. S.29°E., 22 lks. dist., marked C.C., T.1 S., R.36 E., S.18, B.T. Land; high and mountainous. Soil; 2nd and 3rd rate. Heavily timbered with fir, pine, spruce and tamarack, 99.91 chs. Dense undergrowth of fir, pine, spruce and tamarack and mountain laurel.</p>	
Oct. 1st, 1882.	