

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	A pine, 22 ins. diam., brs. N.43°W., 48 lks. dist., marked C.C., T.1 S., R.35 E., S.24, B.T.	
	A pine, 12 ins. diam., brs. S.70° W., 67 lks. dist., marked C.C., T.1 S., R.35 E., S.25, B.T.	
	Land; high and mountainous.	
	Soil; 2nd and 3rd rate.	
	Heavily timbered with fir, tamarack and pine, 91.60 chs.	
	Dense undergrowth of fir, tamarack, pine and mountain laurel.	
	S. bet. Secs. 25 & 26	
	Var. 18°30' E.	
15.00	Top of hill, brs. N.W. & S.E., 150 ft. above Sec. Cor. and near summit of mountains in this Tp.	
18.00	Descend hill, brs. N.W. & S.E.	
32.70	Foster's toll road brs. N.25°W & S.25°E., 100 ft. below summit.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 10 ins. diam., brs. S.40°E., 19 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 10 ins. diam., brs. S.53° W., 19 lks. dist., marked $\frac{1}{4}$ S., B.T.	
43.00	Enter opening, brs. N.W. & S.E.	
45.00	Leave opening and enter timber, brs. N.W. & S.E.	
53.25	Old road brs. E. & W.	
58.32	Fir, 34 ins. diam.	
61.55	Dry gulch, course N.W., 250 ft. below Foster's toll road.	
63.45	Same dry gulch, course N.E.	
65.30	" " " " N.W.	
	And ascend.	
75.20	Enter opening, brs. N.W. & S.E.	
77.50	Leave opening and enter timber, brs. N.W. & S.E.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 25, 26, 35 & 36, 190 ft. above dry gulch, marked,	