

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	A tamarack, 9 ins. diam., brs. N.72°W., 21 lks. dist., marked $\frac{1}{4}$ S., B.T.	
44.50	Enter clearing of right of way, brs. N.10°E & S.10°W.	
48.50	Wagon road, brs. N.W. & S.E., 50 ft. below $\frac{1}{4}$ Sec. Cor.	
50.68	Leave clearing of right of way, brs. N.10°W., & S.10°E.	
60.50	Enter beaver dam bottom on Meacham Creek, N.W. & S.E.	
61.00	Meacham Creek, 10 lks. wide, runs N.W.; 50 ft. below right of way.	
63.00	Leave creek bottom, brs. N.W. & S.E.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 14, 15, 22 & 23, 75 ft. above Meacham Creek, marked, <p style="margin-left: 40px;">T.1 S., R.35 E., S.14 on N.E. T.1 S., R.35 E., S.15 on N.W. S.22 on S.W. and S.23 on S.E. faces with 3 notches on S. and 2 notches on E. edges, from which A fir, 8 ins. diam., brs. N.15°E., 29 lks. dist., marked T.1 S., R.35 E., S.14, B.T. A fir, 5 ins. diam., brs. N.53°W., 27 lks. dist., marked T.1 S., R.35 E., S.15, B.T. A fir, 10 ins. diam., brs. S.77°W., 26 lks. dist., marked T.1 S., R.35 E., S.22, B.T. A fir, 8 ins. diam., brs. S.22°E., 17 lks. dist., marked T.1 S., R.35 E., S.23, B.T.</p> Land; high and mountainous, except bottom level. Soil; on bottom, 1st rate. Remainder, 2nd rate. Heavily timbered with fir, tamarack, pine and spruce, 58.82 chains. Dense undergrowth of fir, tamarack, pine and spruce.	
	E. on a random line bet. Secs. 14 & 23. <p style="margin-left: 100px;">Var. 19°30' E.</p>	
3.00	Cabin brs. S., 50 lks. dist.	
83.22	Dry bed of Meacham Creek, 15 lks. wide, course N., 75 ft.	