

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	Dense undergrowth of pine, fir, tamarack, spruce and mountain laurel. Prairie; 8.30 chs., Scattering pine on remainder on S. 30 chs.	
	E. on random line bet. Secs. 15 & 22. Var. 20° E.	
30.80	Tie road brs. N. & S.	
34.00	Dry bed of creek, 5 lks. wide, in ravine, course N.E., 100 ft. below Sec. Cor. And ascend.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 100 ft. above bed of creek.	
53.00	Top of hill, brs. N. & S., 50 ft. above $\frac{1}{4}$ Sec. Cor.	
61.00	Descend hill, brs. N. & S.	
79.40	Intersect N. & S. line, 70 lks. N. of Cor. to Secs. 14, 15, 22 & 23, 200 ft. below top of hill. Thence I run, N.89° 30' W. on true line bet. Secs. 15 & 22. Var. 20° E.	
39.70	Set post, 5 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor; marked $\frac{1}{4}$ S. on W. face, from which, A pine, 24 ins. diam., brs. N.23° W., 26 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 6 ins. diam., brs. S.56° E., 45 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.40	The Cor. to Secs. 15, 16, 21 & 22. Land; high and mountainous. Soil; 2nd rate. Heavily timbered with pine, fir, tamarack and spruce. Dense undergrowth of pine, fir, tamarack, spruce and mountain laurel.	
	W. bet. Secs. 16 & 21. Var. 20° E.	
22.83	Dry bed of creek, 3 lks. wide, course N., 250 ft. below Sec. Cor.	
24.80	Tie road, brs. N. & S.	