

## Subdivisional Lines; T. 1 S., R. 35 E., W.M.

Chains		Feet
26.60	Dry bed of creek; 8 lks. wide, course N.E.	
29.50	Ascend hill, brs. N.E. & S.W.	
31.46	A pine, 40 ins. diam.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., 100 ft. above bed of creek, marked <math>\frac{1}{4}</math> S. on N. face, from which,</p> <p>A pine, 24 ins. diam., brs. N.53°W., 126 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A pine, 20 ins; diam., brs. S.20° E., 25 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
	Discontinued line at this $\frac{1}{4}$ Sec. Cor. on account of Umatilla Indian Reservation.	
	Land; high and mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with fir, tamarack and spruce, 40 chs.	
	Dense undergrowth of fir, tamarack and spruce.	
	S. bet. Secs. 21 & 22.	
	Var. 20° E.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., 100 ft. above Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which,</p> <p>A fir, 9 ins. diam., brs. N.37° E., 28 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A fir, 8 ins. diam., brs. N.76°W., 46 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
64.00	Top of hill, brs. N.E. & S.W., 100 ft. above $\frac{1}{4}$ Sec. Cor.	
67.00	Descend hill, brs. N.E. & S.W.	
72.50	Dry gulch, course N.E., 100 ft. below top of hill and ascend.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 21, 22, 27 &amp; 28. 150 ft. above dry gulch, marked,</p>	
	T.1 S., R.35 E., S.22 on N.E.	
	T.1 S., R.35 E., S. 21 on N.W.	
	S.28 on S.W. & S.27 on S.E. faces, with	