

S. Bdy. of T.1 S., R.35 E., W.M.

Chains		Feet
	<p>W. bet. Secs. 3 & 34,</p> <p style="text-align: center;">Var. 19°15' E.</p> <p>through a late burn- on level mountain top.</p> <p>40.02 $\frac{1}{4}$ Sec. Cor., a post, marked and witnessed as described by the Surveyor-General and witnessed, burned over, but markings not burned out.</p> <p>79.90 A post, much burned, but marks readable, as follows;</p> <p style="padding-left: 40px;">T.1 S., S.34 on N.E.</p> <p style="padding-left: 40px;">R.35 E., S.3 on S.E.</p> <p style="padding-left: 40px;">T.2 S., S.4 on S.W. and</p> <p style="padding-left: 40px;">S.32 on N.W, faces</p> <p style="padding-left: 40px;">notches burned off.</p> <p>Witness trees found, corresponding to notes furnished by Surveyor-General, all more or less burned, but as there are no green trees within limits, I leave them as I find them.</p>	
	<p>W. on N. Bdy. of Sec.4</p> <p>28.30 A post, 2 ft. high, 4 ins. sq., set firmly in the ground, marked</p> <p style="padding-left: 40px;">C.C., T.1 S., R.35 E., on N.</p> <p style="padding-left: 40px;">S 34 on E. and</p> <p style="padding-left: 40px;">S.33 on W. faces, grooves burned off.</p> <p>Note: I was surprised at finding this Cor., as neither my instructions nor plats, furnished by the Surveyor-General had indicated anything irregular in the subdivisions of T.1 S., R.35 E. and I had not carefully examined the field notes of the same, furnished me, by the Surveyor-General.</p> <p>I, now, find that I cannot follow the letter of instructions as they seem to have been formulated on the presumption that this Tp. was regularly subdivided. As I can't await further instructions for the making this survey, therefore, proceed with the same according to the Manual of Instructions.</p>	