

## South Bdy. of T. 1 S., R. 35 E., W.M.

Chains		Feet
	<p>This Closing Cor. post and witnesses are badly burned, and marks thereon scarcely readable, I, therefore, re-established it.</p> <p>Set tamarack post, 3 ft. long, 4 ins. sq.; 24 ins. in ground for Closing Cor. to Secs. 33 &amp; 34, marked,</p> <p style="padding-left: 40px;">C.C.; T.1 S., R.35 E., on N.</p> <p style="padding-left: 40px;">S.34 on E. and</p> <p style="padding-left: 40px;">S.33 on W. faces, with</p> <p style="padding-left: 40px;">3 notches on E. &amp; W. edges, from which,</p> <p style="padding-left: 40px;">A tamarack, 17 ins diam., brs. N.13°E., 82 lks. dist., marked T.1 S., R.35 E., S.34, B.T.</p> <p style="padding-left: 40px;">A tamarack, 14 ins. diam., brs. N.70° W., 110 lks. dist., marked T.1 S., R.35 E., S.33, B.T.</p> <p>Enter green timber.</p>	
40.00	<p>I do not find any trace of the old Cor., therefore, I set a basalt stone, 17 x 11 x 6 ins., 12 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on N. face, from which,</p> <p style="padding-left: 40px;">A pine, 6 ins. diam., brs. N.8°E., 61 lks. dist., marked <math>\frac{1}{4}</math> S., B.T. and</p> <p style="padding-left: 40px;">A fir, 5 ins. diam., brs. S.19°W., 57 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
56.50	<p>Brow of hill; descend almost perpendicular S.E. face, 1000 ft.</p>	
80.00	<p>Set basalt stone, 17 x 12 x 7 ins., 12 ins. in ground, for Cor. to Secs. 4 &amp; 5, marked with 4 notches on E. and 2 on W. edges and raised a mound of stone, 2 ft. at base, 1<math>\frac{1}{2}</math> ft. high, S. of Cor. Pits impracticable.</p> <p>Land; mountainous.</p> <p>Soil; loam, 3rd rate.</p> <p>Timber; heavy pine, fir, tamarack and spruce, burned 28.30 chs., green; 28.18 chs.</p> <p>Mountainous land, 80 chs.</p>	
	<p>W. on N. Bdy. of Sec. 5</p> <p>Descend very steep, rocky S.E. face.</p>	
.20	<p>Creek, 17 lks. wide, course N.20°W., ascend very steep N.E.</p>	