

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	S. to retrace the line bet. Secs. 27 & 28; ascend gradual.	
3.00	Summit of hill, brs. N.W. & S.E. along hilltop.	
12.50	Brow, descend S. face.	
31.00	Foot of hill, brs. E. & W. enter bottom land.	
32.57	Creek, 7 lks. wide, course N.W. Ascend.	
33.25	Foot of hill, brs. S.E. & N.W. Enter dense young timber and ascend.	
40.02	Post is gone, but I find both witness trees in good condition; to re-establish this Cor., I Set tamarack post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, with same witnesses, to-wit: A tamarack, 4 ins. diam., brs. 52°E., 10 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 6 ins. diam., brs. N.36°W., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.	
40.80	A pine, 40 ins. diam., line tree, marked with 2 notches in N. & S. sides.	
60.00	Summit of hill, brs. N.W. & S.E., 150 ft. above last creek descend, scattering timber.	
80.11	Find post, lying down, much decayed; all witnesses gone or dead, excepting the one in Sec. 34. At Cor. point, as indicated by the remaining witnesses and blazes, to re-establish this Cor., I Set a tamarack post, 3 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 27, 28, 33 & 34, marked T.1 S., S.27 on N.E. R.35 E., S.34 on S.E. S.33 on S.W. and S.28 on N.W. faces, with 1 notch on S. and 3 " " E. edges, from which, A tamarack, 6 ins. diam., brs. N.22° E., 17 lks. dist., marked T.1 S., R.35 E., S.27, B.T. A pine, 12 ins. diam., brs. S.18°E., 116 lks. dist., marked T.1 S., R.35 E., S.34, B.T.	