

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>Secs. 8, 9, 16 &amp; 17, marked</p> <p>T.1 S., R.35 E., S.8 on N.W.</p> <p>S.9 on N.E.</p> <p>S.16 on S.E. and</p> <p>S.17 on S.W.</p> <p>4 notches on S. &amp; E. edges, from which,</p> <p>A fir, 20 ins. diam., brs. N.65°E., 24 lks. dist.,</p> <p>marked T.1 S., R.35 E., S.9, B.T.</p> <p>A fir, 16 ins. diam., brs. S.35° E., 159 lks. dist.,</p> <p>marked S.16, B.T.</p> <p>A fir, 24 ins. diam., brs. S.10°W., 130 lks. dist.</p> <p>marked S.17, B.T.</p> <p>A fir, 20 ins. diam., brs. N.70°W., 23 lks. dist.,</p> <p>marked S.8, B.T.</p> <p>Land; rolling, covered with heavy pine, fir and tamarack timber and underbrush, 60 chs.</p> <p>Good grass in openings.</p> <p>Soil; 3rd rate.</p>	
	<p>E. on random bet. Secs. 9 &amp; 16.</p> <p style="text-align: right;">Var. 20°E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
66.90	To U.R.Bdy., set temp. M.C.	
80.65	Intersect N. & S. line at Cor. to Secs. 9, 10, 15 & 16.	
	which I found in good condition.	
	Thence I run	
	W. on true line.	
3.00	Meacham Creek, 8 lks. wide, course N.	
13.75	Set post, 48 x 4 x 4 ins., 24 ins. in ground for M.C.,	
	marked U.R.M.C. on W. face, from which,	
	A pine, 10 ins. diam., brs. N.45°E., 97 lks. dist.,	
	marked U.R.M.C.B.T.	
	A pine, 5 ins. diam., brs. S.40°E., 152 lks. dist.,	
	marked U.R., M.C., B.T.	
	Cor. stands S.20°W., dist. 19.46 chs. from 52nd Mile Cor.	
	on U.R.Bdy.	