

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	of medium size. Huckleberries and pine grass, 69.00 chs. Soil; 2nd rate.	
	E. on random bet. Secs. 8 & 17. Var. 22°15' E..	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.15	Intersect N. & S. line, 26 lks. S. of Cor. to Secs. 8, 9, 16 & 17. Thence I run S. 89°49' W. on true line	
15.00	Wagon road, course N.W. & S.E.	
40.07	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, from which, A pine, 4 ins. diam., brs. N. 15° E., 20 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 8 ins. diam., brs. N. 45° W., 45 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.15	To Cor. to Secs. 7, 8, 17 & 18. Land; rolling, covered with heavy pine timber. Soil; 2nd rate., 80.15 chs.	
	W. on true line bet. Secs. 7 & 18. Var. 22° 15 ' E.	
5.00	Enter thick timber.	
20.00	Leave timber.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, from which, A pine, 24 ins. diam., brs. N. 50° E., 78 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 16 ins. diam., brs. S. 45° E., 67 lks. dist., marked $\frac{1}{4}$ S., B.T.	
47.00	Intersect Tp. line, 4.70 chs. N. of Cor. to Secs. 12 & 13. Set basalt stone, 12 x 10 x 18 ins., 8 ins. in ground, for Closing Cor. to Secs. 7 & 18, marked C.C. with 4 notches on S. and 2 on N. edges; raised stone mound around it. Pits impracticable.	