

## Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		feet
80.00	Intersect N. & S. line at Cor. to Secs., 16, 17, 20 & 21.	
	Thence I run	
	W. on true line	
12.50	Wagon road, course S.E. & N.W.	
13.00	Gulch, course N.W.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor.	
	marked $\frac{1}{4}$ S on N. face, from which,	
	A fir, 20 ins. diam., brs. N. 42° E., 14 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
	A fir, 20 ins. diam., brs. N. 42° W., 33 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
65.70	Head of draw, course N.W.	
80.00	To Cor. to Secs. 17, 18, 19 & 20	
	Land; rolling, covered with pine and spruce timber and	
	underbrush. Good grass in openings.	
	Soil; 2nd rate.	
	W. on true line bet. Secs. 18 & 19	
	Var. 19° E.	
9.80	Indian trail, course S.E.	
22.80	Thick timber.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor.	
	marked $\frac{1}{4}$ S. on N. face, from which,	
	A pine, 5 ins. diam., brs. S. 60° E., 45 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
	A pine, 20 ins. diam., brs. N. 45° W., 34 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
47.24	Intersect Tp. line, 5.29 chs. N. of Cor. to Secs. 13 & 24	
	Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Closing	
	Cor. to Secs. 18 & 19, marked	
	T. 1 S., R. 34 E., S. 13 on W. face	
	T. 1 S., R. 35 E., S. 18 on N.E.	
	S. 19 on S.E. and	
	3 notches on N. & S. edges and	
	G.C. on W., from which,	
	A pine, 16 ins. diam., brs. N. 80° E., 44 lks. dist.	