

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
33.75	Draw, course N.W.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, from which, A pine, 24 ins. diam., brs. N.30°E., 85 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 6 ins. diam., brs. S.10°W., 15 lks. dist., marked $\frac{1}{4}$ S., B.T.	
45.40	Leave timber.	
80.00	To Cor. to Secs. 19, 20, 29 & 30. Land; rolling, covered with open pine and tamarack timber and good grass in prairie. Soil; 2nd rate.	
W. on true line bet. Secs. 19 & 30. Var. 19°15' E.		
12.50	Begin to descend.	
33.75	Canyon, course S.	-600
40.00	Set basalt stone, 14 x 12 x 8 ins., 10 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S., on N. face; raised mound of stone alongside. Pits impracticable.	+200
49.05	Intersect Tp. line, 5.84 chs. N. of Cor. to Secs. 24 & 25 Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Closing Cor. to Secs. 19 & 30, marked, 2 notches on S., 4 notches on N. edges and C.C. on E. face; raised a mound of stone around it. Pits impracticable. Land; broken mountains, 49.05 chs. No timber, good grass. Soil; 3rd rate.	+300
July 2nd, 1887.		
S. bet. Secs. 29 & 30 Var. 19° 15' E.		
10.00	Leave table land; descend.	
15.00	Descend rimrock, 40 ft.	
26.00	Gulch, course S.W.	-200
40.00	Set basalt stone, 20 x 12 x 6 ins., 15 ins. in ground, for	