

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face; raised stone mound around it. Pits impracticable.	-150
40.75	Gulch, course S.W.	-400
62.75	McKay Creek, 15 lks. wide, W.	-500
80.00	Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 29, 30, 31 & 32, marked 1 notch on S. and 5 notches on E. edges; raised mound of stone around it. Pits impracticable.	-800
	Land; extremely rough and mountainous, 80 chs.	
	Soil; rocky, 4th rate.	
	Scattering pine timber on S. side of canyon, bunch grass on N. side.	
	E. on true line bet. Secs. 29 & 32.	
	Var. 19°30' E.	
8.47	Gulch, course N.	-200
17.60	Summit, enter timber	-100
30.75	Creek, 5 lks. wide, course N.	-500
40.00	Set basalt stone, 10 x 10 x 8 ins., 7 ins. in ground, in small glade, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raised stone mound around it. Pits impracticable.	-150
59.50	Intersect U.R.Bdy., 5.63 chs., N. 20° E. of 55 $\frac{1}{2}$ M. post.	
	Set basalt stone, 20 x 16 x 8 ins., 15 ins. in ground, for Closing Cor. to Secs. 29 & 32, marked U.R.C.C. on W. face; raised stone mound around Cor. All trees in limits deadened by fire. Pits impracticable.	
	Land; mountainous, 59.50 chs. Line running on steep side of canyon.	
	Soil; rocky, 4th rate.	
	Pine, fir and tamarack timber.	
	W. on true line bet. Secs. 30 & 31.	
	Var. 19°30' E.	
20.30	Canyon, course N.W.	-400
33.00	Summit " "	-300
40.00	Set basalt stone, 9 x 8 x 7 ins., for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$	