

Subdivisional Lines; T.1 S., R.35 E., W.M.

Chains		Feet
66.90	To U.R.Bdy.; set temp. C.C.	
80.65	Intersect N. & S. line at Cor. to Secs. 9, 10, 15 & 16, which I found in good condition. Thence I run W. on true line Var. 20° E.	
3.00	Meacham Creek, 8 lks. wide; course N.	20
13.75	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Closing Cor. on U.R.Bdy.; marked U.R.C.C. on W. T.1 S., R.35 E., S.16 on S. S.9 on N. faces, from which, A pine, 10 ins. diam., brs. N.45° ^W , 97 lks. dist., marked T.1 S., R.35 E., S.9; U.R.C.C., B.T. A pine, 5 ins. diam., brs. S.40°E., 152 lks. dist., marked T.1 S., R.35 E., S.16, U.R.C.C., B.T. This Cor. stands S.20°W., 19.46 chs. dist. from 52nd ^M .Cor. on U.R.Bdy.	
20.00	Summit of hill	
40.32	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A tamarack, 5 ins. diam., brs. S.50°E., 130 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 16 ins. diam., brs. S., 2 lks. dist., marked $\frac{1}{4}$ S., B.T.	
52.30	Gulch, course N.W.	
80.65	To Cor. to Secs. 8, 9, 16 & 17. Land; rolling. Soil; 3rd rate. Open pine, fir and tamarack timber with huckleberry and snow brush.	
	S. bet. Secs. 16 & 17. Var. 20°E.	
32.70	Wagon road; course N.W. & S.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$	