

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>timber. Good bunch grass and pine grass in openings. Soil; 3rd rate.</p>	
	<p>S. on true line bet. Secs. 28 &amp; 29. Var. 19°E.</p>	
20.28	<p>U.R.Bdy., 11.55 chs., S.20°W. of 54½ M. post on U.R.Bdy. I faced the four sides of a fir tree, 10 ins. diam., for Closing Cor., which I marked U.R., C.C. on N. T.1 S., R.35 E., S.29 on W. S.28 on E. faces. Raised mound of stone alongside tree. Land; level, covered with scattering pine and fir timber. Good grass. Soil; 3rd rate. Surveyed June 30, 1887.</p>	
	<p>From the Cor. of Secs. 5, 6, 31 &amp; 32 on the Base Line, I run S. bet. Secs. 5 &amp; 6. Var. 19° E.</p>	
30.00	<p>Leave open timber, enter prairie.</p>	
39.00	<p>Set basalt stone, 14 x 12 x 9 ins., 9 ins. in ground, for Sec. Cor., marked 4 on W. face; raised mound of stone alongside. Pits impracticable.</p>	
60.00	<p>Enter thicket.</p>	
75.00	<p>Leave thicket, enter pine opening.</p>	
79.00	<p>Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 5 &amp; 6, 7 &amp; 8, marked, 5 notches on S. &amp; E. edges, from which, A pine, 18 ins. diam., brs. S.75°E., 105 lks. dist., marked T.1 S., R.35 E., S.8, B.T. A pine, 36 ins. diam., brs. N.39°E., 195 lks. dist., marked T.1 S., R.35 E., S.5, B.T. A pine, 20 ins. diam., brs. N.32°W., 40 lks. dist., marked T.1 S., R.35 E., S.6, B.T. A pine, 22 ins. diam., brs. S.84°W., 50 lks. dist.,</p>	