

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	W. on true line bet. Secs. 19 & 30. Var. 19°15' E.	
12.50	Begin to descend.	
33.75	Canyon, course S.	60
40.00	Set basalt stone, 12 x 8 x 14 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raised mound of stone alongside. Pits impracticable.	200
49.05	Intersect Tp. line, 5.84 chs., N. of Cor. to Secs. 24, 25, T.1 S., R.34 E. Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Closing Cor. to Secs. 19 & 30, marked with 2 notches on S. 4 notches on N. edges and C.C. on E. face; raised mound of stone a- round it. Pits impracticable.	300
	Land; broken, mountainous, 49.05 chs. Good bunch grass. Soil; 3rd rate. Surveyed- July 2nd 1887.	
	S. bet. Secs. 29 & 30. Var. 19°15' E.	
10.00	Leave table land; descend.	
15.00	Descend rimrock 40 ft.	
26.00	Gulch, S.W.	200
40.00	Set basalt stone, 20 x 12 x 6 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; raised mound of stone around it. Pits impracticable.	150
40.75	Gulch, c. S.W.	400
62.75	McKay Creek, 15 lks. wide, course W.	500
80.00	Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground for Cor. to Secs. 29, 30, 31 & 32, marked with 1 notch on S. 5 notches on E. edges, raised mound of stone around it. Pits impracticable.	800
	Land; extremely rough and mountainous, 80.00 chs.	